Title Mike Rylko Park In-Line Rink 02/26/2024

by Timothy Howe in Member District ADA Project Request

id. 45685394

530 Bernard Dr Buffalo Grove, Illinois **United States** 8478502163 thowe@bgparks.org

Original Submission

02/26/2024

Score	n/a
Name	Tim Howe
Job Title	Director of Parks and Planning
E-mail Address	thowe@bgparks.org
Phone Number	8478502100
Park District	Buffalo Grove
Project Location	Mike Rylko Park In-Line Rink
Project Status	Alteration
Project Type	Routes and Surfaces
Routes and Surfaces- select a Project Category below:	Walking Surfaces Accessible Routes- Means of Egress
Benefits of the Project	Accessible pathways leading to the in-line rink.
Items that will become ADA Compliant	Pathways to access the in-line rink
The project is designed or constructed, or applies human resources, to comply with:	The 2010 Standards for Accessible Design

Upload Project Related Files, Photos, Videos or Audio

Upland_Design_InLine.pdf

Hacienda_InLine.pdf

In-Line_Rink_Drawing.pdf

Budget Table for ADA Related Expenses

Budget Table.xlsx

ADA Dollars Requested 32372.5

Notes related to requested amount



BID FORM 1 of 3

Proposal of Haciend partnership, individual)	a landerapinglereinafter called "BIE	DDER", (a)/ (an) (corporation,
Doing business as + COLOR Park District, herein after calle	nda landscaping \nc	to the Buffalo Grove
the Specifications, Drawings, a materials and supplies in accor	r advertisement for bids of the 2023 RYLKO PARK and other contract documents, hereby proposes to dance with the Contract Documents, within the tirprices are to cover all expenses including delivery	furnish and deliver all ne set forth there in and at
Bidder acknowledges receipt o	f the following Addenda(s), which is (are) a part of	the Contract Documents:
Number(s):	<u> </u>	
Base Bid for all work:	s 418,278 [™]	
Alternate #A Bid for all work:	s 76,369 [™]	
Alternate #B Bid for all work:	s ≤9,900°°	
Alternate #C Bid for all work:	\$ 17,000	
Alternate #D Bid for all work:	s 29,780 °°	,
nclude completed Unit Cost W	orksheet.	
Warranty Period:	lears.	
Bidder hereby agrees to start w	ork within ten (10) calendar days after receipt of "[Notice to Proceed" from the

Bidder hereby agrees to start work within ten (10) calendar days after receipt of "Notice to Proceed" from the Owner and to substantially complete the project as specified in the Project Identification and Schedule.



BID FORM 2 of 3

Important Note— To the extent it applies, Contractor must comply with requirements of the Illinois Prevailing Wage Act. Copies of the Labor Standards Provisions and the most recent Department of Labor Wage Determination can be found on the Department of Labor web site.

Bidder agrees to perform all of the work specified and required by the proposed contract documents. Accompanying bid is a 10 % Bid Bond (in the form of a Bid Bond, Certified Check or Cashier's Check) in the amount of (\$ 2000 0), the same being subject to forfeiture in the event of default by the undersigned.

In submitting this bid, it is understood that the right is reserved by the Owner to reject any and all bids and it is agreed that this bid may not be withdrawn during the period of days provided in the Contract Documents.

The Bidder here by certifies:

- A. That this bid is genuine and is not made in the interest of or on behalf of any undisclosed person, firm or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation.
- B. That he/she has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid.
- C. That he/she has not solicited or induced any person, firm, or corporation to refrain from bidding.
- D. That he/she has not sought by collusion or otherwise to obtain for him any advantage over any other didder or over the "Owner"
- E. That he/she, to the extent that it applies, must comply with requirements of the Illinois Prevailing Wage Act.
- F. That he/she is in compliance with the Criminal Code Act of1961, ArticleE-11, Public Contracts, and Public Act 85-1295.
- G. That all materials, methods and workmanship shall conform to the General Conditions and Performance Specifications.



BID FORM 3 of 3

	Buffalo Grove Park District	Hacienda landscaping Inc.
	(Owner)	(Contractor)
	530 Bernard Drive	DAYD Grove Rd
	(Address)	(Address)
	Buffalo Grove, IL 60089	MIDROKA IT (OR44)
	(City/State/Zip)	(City/State/Zip)
	847-850-2100	81S-577-0XS1
	(Phone)	(Phone)
BY:	Ryan Risinger	BY: May Sulla
	(Sigh)	(Sign)
	Ryan Risinger	Maria Lunman
	(Print Name)	(Print Name)
	01/24/2023	12/19/2
	(Date)	(Date

contractor: laclenda Lanciscaping inc

TO:

Buffalo Grove Park District 2023 Rylko Park Improvements 530 Bernard Drive Buffalo Grove, Illinois 60098

Project #1086 rebid

The undersigned bidder has carefully examined the plans and specifications for Raupp Museum Nature Classroom Development Phase II, in Buffalo Grove, Illinois as prepared by Upland Design Ltd. and having carefully examined the site and completely familiarized him/herself with local conditions affecting the cost of the work: hereby states that he/she will provide all necessary labor, equipment, tools, machinery, apparatus and all other means of construction, do all the work and furnish all materials, called for by said plans and specifications in the manner prescribed by in accordance with the requirements of the contract, specification and drawings: and will accept as full and complete payment therefore the base bid amount which is the summation of the cost of the items of work and is equal to the summation of the extension of the unit prices.

Description of abbreviations:

SF = Square Feet

CF = Cubic Feet

LF= Lineal Feet

SY = Square Yard

CY = Cubic Yard

LS = Lump Sum

FF = Finished Face

BASE BID - RAUPP NATURE CLASSROOM DEVELOPMENT PHASE II

	TOTAL SERVICE OF SOCIOOUS DE VECOPINENT PRASE II						
item #	Description	Quantity	Unit	Installed Unit	Item Total		
1	Site Preparation, Removals & Earthwork, Complete	1	LS	\$28,000	\$ 28,000		
2	Silt Fence	92	ĹF	\$ 4	\$ 368		
3	Temporary Concrete Washout	1	LS	\$ 600	\$ 600		
4	Concrete Paving	97	SF	\$12	\$ 1,164		
5	Concrete Paving - Integral Color	374	SF	\$ 14	\$ 5,236		
6	Stamped Concrete Paving (With Integral Color)	2906	SF	\$ 16	\$ 46,496		
7	Split Rail Fence	151	LF	\$39	\$ 5,889		
8	Raised Curb Planter	64	LF	\$ 40	\$2,560		
9	Sculpture Footing	1	LS	\$350	\$350		
10	Limestone Steppers	1	LS	\$2,500	\$2,500		
11	Pollinator Wall Footing	1	EA	\$ 450	\$ 4_50		
ite Fur	niture shall be purchased and fully installed b	y Contrac	tor.		100 . 4		
12	Picnic Table	6	EA	\$ 1,850	\$ 11,100		
13	Picnic Table ADA	2	EA :	\$ 1,950	\$ 3,900		

contractor: Hadepda landscaping Inc

					IDDIVI
14	Log Bench	2	EA	\$5,200	\$ 10,400
15	Topsoil Fill for Planters - 12" Depth	3	CY	\$ 1.50	\$ 450
16	Dieciduous Shrubs	36	EA	\$ 160	\$ 5,760
17	Ornamental Grasses	216	EA	\$ 30	\$ 6,480
18	Perennials	482	EA	\$ 30	\$ 14,460
19	Landscape Boulders	1	LS	\$3,500	\$ 3,500
20	Native Seed Mix	1	LS	\$ 2,000	\$ 2,000
21	Sod	1	LS	\$ 8,000	\$ 8,000
22	Lawn restoration and establishment including core aeration, seeding, fertilizing, and blanket cover at all disturbed areas.	1	LS	\$ 9,000	\$ 9,000

Raupp Museum Nature Classroom Development
Phase II SUBTOTAL \$ 168,663

BASE BID - INLINE SKATE RINK REDEVELOPMENT

	THE PROPERTY OF THE PROPERTY O				
ltem #	Description	Quantity	Unit	Installed Unit Price	Item Total
23	Inlet Baskets	2	EACH	\$350	\$ 700
24	Inlet Baskets and Coir Log	6	EACH	\$ 600	\$ 3,600
25	Coir Log	1	EACH	\$ 1,50	\$150
26	Concrete Washout	1	LS	\$ 600	\$ 600
27	Temporary Construction Fence	1095	LF	\$ 8	\$ 8,760
28	Silt Fence	340	LF		\$1,360
	Tree Trunk Protection	9	EACH	\$ 250	\$2,250
30	Unsuitable Removal and Replacement with PGE (Allowance)	150			\$ 12,000
31	Bench and Bleacher Removal	1	LS	\$ 800	\$ 800
32	Full Depth Asphalt Removal	2031	SY		\$ 46,713
33	HMA Pathway Removal	185	SY		\$ 3,700
34	Concrete Curb Removal	507	LF		\$ 6,084
	Sawcut Pavement, Full Depth	745	LF		\$ 745
	Dasher Board & Rink Fence Removal and Disposal	507	LF :	\$ 14	\$ 7,098
37 F	Perimeter Fence Removal and Disposal	520	LF :	12	\$ 6,240

contractor: Hadlenna landscapin


ed PVC, 4 Inch	530	LF	\$25	\$ 13.250
orated PVC, 4 Inch	59	LF	\$25	\$ 1,475
/C, 6 Inch	167	ĻF	\$ 32	\$ 5,344
& Lid	4	EACH	\$ 400	\$ 1,600
pen Lid	2	EACH	\$ 2,500	\$ 5,000
T1 Closed Lid	1	EACH	\$ 4,000	\$ 4.000
ion	1	EACH	\$ 600	\$ 600
	25	LBS	\$ 27	\$ 675
Rink, 1.75 Inch	18	TON	\$ 140	\$2,520
Rink, 2.25 Inch	24	TON	\$ 145	\$ 3,480
Path, 3 Inch	148	TON	\$155	\$ 22,940
	850	SF	\$ 12	\$10,200
(Allowance)	350	SF	\$13	\$4,550
se, Rink, CA-6, 4 Inch	192	SY	\$18	\$ 3,456
e, Paths, CA-6, 4 Inch	972	SY	s 6	\$15,552
ain Backfill - CA-7	125	CY	\$ 80	\$ 10,000
	115	LF	\$45	\$ 5,175
ches, Furnished by	1 500	DE	\$ 2,000	\$ 2.000
ace, 6 Inch Min.	1185	\$Y	\$ 14	\$16,590
00sf	11	LBS	\$ 56	\$ 616
rance	266	SY	\$ 12	\$3,192
Sign	1	LS :	600	\$ 600
	ed PVC, 4 Inch forated PVC, 4 Inch VC, 6 Inch e & Lid Dpen Lid T1 Closed Lid tion Rink, 1.75 Inch Rink, 2.25 Inch Path, 3 Inch t (Allowance) se, Rink, CA-6, 4 Inch rain Backfill - CA-7 8 (Special) iches, Furnished by ace, 6 Inch Min. NOOsf rance Sign	forated PVC, 4 Inch VC, 6 Inch 8 & Lid 4 Deen Lid T1 Closed Lid 1 tion 1 25 Rink, 1.75 Inch Rink, 2.25 Inch Path, 3 Inch 1 48 59 1 (Allowance) 350 se, Rink, CA-6, 4 Inch se, Paths, CA-6, 4 Inch (Special) 1 (Special)	forated PVC, 4 Inch VC, 6 Inch E & Lid Dee & Lid Dee Lid T1 Closed Lid T1 Closed Lid T1 EACH E	forated PVC, 4 Inch Forated PVC, 6 Inch Forated PVC, 4 Inch Forated PVC, 4 Inch Forated PVC, 6 Inch Forated PVC, 6 Inch Forated PVC, 6 Inch Forated PVC, 4 Inch Forated PVC, 6 Inch Forated P

inline Skate Rink SUBTOTAL \$ 249, 615

Base Bid - 2023 Rylko Park Improvements TOTAL $$418,278^{\circ\circ}$$

Base Bid - 2023 Rylko Park Improvements in Writing:

Four Hundred Fighteen Thorsand Two Hundred and Seventy Eight Pollars 00/100



ALTERNATE #A: Alcott Improvements

	Description	Quantity	Unit	Installed Unit Price	item Total
Add A-1	Sawcut, Full Depth	50	LF	\$2	\$ 100
Add A-2	Earth Excavation	1	LS	\$ 12,000	\$ 12,000
Add A-4	Tree Trunk Protection	9	EA	\$ 250	\$ 2,2,50
Add A-5	HMA Pathway Removal	440	SY		\$ 8,800
Add A-6	Fence, Gate and Foundation (Full Depth) Removal	1	LS	\$ 500	\$500
Add A-7	HMA Surface Course, Path, 3 Inch	117	TON	\$ 220	\$ 25,740
A-7	Sidewalk, PCC, 5 Inch	860	SF	\$ 12	\$ 10,320
A-0	Aggregate Base Course, Paths, CA-6, 4 Inch	793	SY	\$ 13	\$ 10,309
A-9	Flat Curb, PCC, 12x12	75	LF	\$.38	\$2,850
Add A-10	Turfgrass Restoration	1	LS	\$3,500	\$ 3, 500

Alternate Bid Total \$ 76,369 00

Alternate Bid in Writing:

Seventy Six Thousand Three Hundred and Sixty Nine Dollers

ALTERNATE #B: Shade Structure and Wall

	D'escription	Quantity	Unit	Installed Unit Price	Item Total
D*	Shade Structure	1	LS	\$ 37,000	\$ 37,000
Add B-2	Wall	30	LF	\$ 600	\$ 18,000
Add B-3	Bench	2	EA	\$2.450	\$ 4,900

Alternate Bid Total \$ 59,900 =

Alternate	Bld in	Writing:		
TIL	A :		3	

Fifty Nine Thousand and Nine Hundred Dollars

Contractor:	Haciena	la Ja	nd < caping
_			

ALTERNATE #C: Water Feature

Description	Quantity	Unit	Installed Unit Price	Item Total
Remove hydrant and replace with water control valve	1	LS	\$5,000	\$ 5,000
Water Feature including concrete paving, water line connection, and landscape boulders	1	LS	\$ 12,000	\$ 12,000

	Alternate Bid Total \$ \ 7,000	
Alternate Bld In Writing: Seventeen Thousand	Dollars 00/100	_

ALTERNATE #D: Asphait Path Improvements

Item #	Description	Quantity	Unit	Installed Unit Price	Item Total
Add D-1	Bench and Site Furniture Removal and Reinstallation	1	LS	\$ 500	\$ <00
Add D-2	HMA Pathway Removal	450	SY	\$ 20	\$ 9000
Add D-3	HMA Surface Course, Path, 3 Inch	80	TON	\$ Z16	\$ 17,280
Add D-4	Turfgrass Restoration	1	LS	\$ 3,000	\$ 3,000

Alternate Bid Total \$ 29,780 00

Alternate Bid in Writing:

Twenty Nine Thousand Seven Hundred and Fighty Dellacs 00

End of Bid Items - Fill out remainder of forms.


Provide 2 copies of bid form.


CONTRACTOR: HALL AND SIGNATURE:


PHONE SSS FAX: A


ADDRESS: DSUD Grove R


List Surety Company Which Contraptor will be using for Performance and Payment Bonds:

















SESC LEGEND

TOPSOIL FURNISH AND PLACE, 6" MIN. SEEDING, CLASS 1, SEED RATE 8 LBS/1000 SF, PENN MULCH

ROCK CONSTRUCTION ENTRANCE





STORM SEWER INLET PROTECTION:



INLET FILTER BASKET



- INLET FILTER BASKET & COIR LOG



COIR LOG



CONCRETE WASHOUT

- 1. OWNER FILES NOTICE OF INTENT (NOI) AT LEAST 30 DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION
- 2. INSTALLATION OF SOIL EROSION AND SEDIMENT CONTROL MEASURES.
- ORANGE CONSTRUCTION FENCING AND/OR SILT FENCE AROUND WETLANDS AND OTHER AREAS NOT TO BE
- PERIMETER SILT FENCE.
- STABILIZED CONSTRUCTION ENTRANCE WITH WASH RACK. • INLET PROTECTION ON EXISTING STRUCTURES CLOSE TO THE DISTURBED AREA.
- 3. CONTRACTOR PERFORMS WEEKLY AND "AFTER RAIN EVENT" INSPECTIONS STARTING UPON DISTURBANCE OF THE SITE (DEMOLITION OR INSTALLATION OF SOIL EROSION AND SEDIMENT CONTROL MEASURES).
- 4. DEMOLITION
- 5. TREE REMOVAL WHERE NECESSARY (CLEAR & GRUB).
- 6. CONSTRUCT SEDIMENT TRAPPING DEVICES (SEDIMENT TRAPS, BASINS AND SEDIMENT REMOVAL CHANNELS).
- 7. DEWATER INTO SEDIMENT REMOVAL CHANNEL, WHICH DISCHARGES TO AN UPLAND AREA. THE HOSE IN THE AREA BEING DEWATERED MUST BE ATTACHED TO A FLOATING DEVICE WITH A SCREEN.
- 8. CONSTRUCT DETENTION FACILITIES AND OUTLET CONTROL STRUCTURE WITH RESTRICTOR AND TEMPORARY PERFORATED RISER. PERMANENTLY STABILIZE THE AREA WITH TOPSOIL, SEED AND EROSION CONTROL BLANKET.
- 9. CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING PLANT GROWTH IN BOTTOM AND SIDE SLOPES OF BASIN. DEWATERING, AS NEEDED, SHALL BE INCIDENTAL TO THE CONTRACTOR'S SCOPE. 10. ABANDON THE EXISTING SITE STORM DRAINAGE; PROTECTION OF POINTS OF ENTRY INTO EXISTING STORM
- 11. STRIP TOPSOIL, STOCK TOPSOIL AND GRADE SITE.
- 12. TEMPORARY CONTAINMENT OF SOIL/AGGREGATE STOCKPILES (SEED AND SILT FENCE AROUND TOE OF SLOPE).
- 13. INSTALL UTILITIES AND ASSOCIATED INLET & OUTLET PROTECTION.
- 14. CONSTRUCT BUILDING AND PAVEMENT.

15. FINE GRADE.

- 16. INSTALL TOPSOIL, SEED, AND PERMANENT EROSION CONTROL
- 17. REMOVE TEMPORARY EROSION CONTROL MEASURE ONLY WHEN SITE HAS ACHIEVED FULL STABILIZATION.
- 18. OWNER TO FILE NOTICE OF TERMINATION (NOT).

SEDIMENTATION AND EROSION CONTROL NOTES

- A. THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS COMPRISED OF THE SOIL REOSION AND SEDIMENT CONTROL PLANS, THE STANDARD DETAILS, THE PLAN NARRATIVE, PLUS THE PERMIT AND ALL SUBSEQUENT
- B. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE (SWPPP) AND THE ILLINOIS GENERAL CONSTRUCTION PERMIT (ILR10) AND BECOME FAMILIAR WITH

GRAPHIC SCALE

(IN FEET) 1 inch = 20 ft.

- C. BEST MANAGEMENT PRACTICES (BMP'S) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY, PROJECT ENGINEER OR OWNER.
- D. PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS MUST BE
- E. GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING AREA, AND AREA FOR
- G. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND
- H. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READLY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED. WATER USE MUST NOT CAUSE ADDITIONAL EROSION.
- J. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
- K. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE (SWPPP), SHALL BE INITIATED AS SOON AS PRACTICABLE.
- L. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT, WASHING SHALL BE IMPLEMENTED AND PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.
- M. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED BY THE END OF THE DAY.
- N. ON-SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE PLAN AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.
- O. ERODIBLE STOCKPILES MUST BE ENCLOSED WITH SILT FENCE BY THE END OF THE WORK DAY.
- P. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES
- Q. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD
- R. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS AND THE USE OF TEMPORARY OR PERMANENT
- S. SOIL EROSION AND SEDIMENT CONTROL FEATURES SHALL BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF HYDROLOGIC DISTURBANCE OF UPLAND AREAS.
- T. DISTURBED AREAS SHALL BE STABILIZED WITH TEMPORARY OR PERMANENT MEASURES WITHIN 7 CALENDAR DAYS OF THE END OF ACTIVE HYDROLOGIC DISTURBANCE OR REDISTURBANCE.
- U. ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE PROPERTY OWNER SHALL ULTIMATELY BE RESPONSIBLE FOR MAINTAINENCE AND REPAIR.

SHEET NUMBER:

of 12 sheets

- V. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION. DISCHARGES SHALL BE ROUTED THROUGH AN EFFECTIVE SEDIMENT CONTROL MEASURE (e.g. SEDIMENT TRAP, SEDIMENT BASIN, OR OTHER APPROPRIATE MEASURE).
- W. THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER OR GOVERNING AGENCY.


N ▲ NASSOCIATES, INC. 625 Forest Edge Drive Vernon Hills, IL. 60061 TEL 847.478.9700 FAX 847.478.9701


COPYRIGHT NOTICE This drawing is the property of Gewalt-Hamilton Assoc., Inc. and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from Gewalt-Hamilton Associates, Inc.

SOIL EROSION & SEDIMENT CONTROL PLAN

2023 RYLKO PARK IMPROVEMENTS - INLINE SKATE RINK REDEVELOPMENT **BUFFALO GROVE PARK DISTRICT BUFFALO GROVE, ILLINOIS**

								FILE: 4647.156 PR1.dwg		
								DRAWN BY: DGC		
								DATE: 12-05-22	4647.155	
								CHECKED BY: JMB		
NO.	BY	DATE	REVISION	NO.	BY	DATE	REVISION	DATE: 12-05-22	1"=20"	





GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL BE PERFORMED ACCORDING TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" LATEST EDITION, THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" LATEST EDITION, THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS" LATEST EDITION THE ILLINOIS PLUMBING CODE. THE DETAILS IN THESE PLANS. THE CONTRACT DOCUMENTS, ALL APPLICABLE REQUIREMENTS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION, THE IEPA AND ORDINANCES OF AUTHORITIES HAVING JURISDICTION AND ALL ADDENDA THERETO.
- EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE AND UTILITIES WITHIN PUBLIC RIGHTS-OF-WAY ARE SHOWN ON THE PLANS ACCORDING TO AVAILABLE RECORDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION IN THE FIELD OF THESE UTILITY LINES AND THEIR PROTECTION FROM DAMAGE DUE TO CONSTRUCTION OPERATIONS. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT WITH NEW CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.
- WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OR UNSUITABLE MATERIALS CREATED AS A RESULT
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE PRIOR TO ORDERING MATERIALS. IN ADDITION, THE CONTRACTOR MUST VERIFY THE LINE AND GRADES. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS 7. SHOWN ON THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS AND/OR SPECIAL DETAILS. THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTION FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSION OR DISCREPANCIES. FAILING TO SECURE SUCH INSTRUCTION, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT HIS/HER OWN RISK AND EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY COSTS INCURRED.
- ALL PAVEMENT DIMENSIONS ARE SHOWN TO EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE THE MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER. AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 72 HOURS PRIOR TO BEGINNING WORK.
- 8. IF DURING CONSTRUCTION THE CONTRACTOR ENCOUNTERS OR OTHERWISE BECOMES AWARE OF ANY SEWERS OR UNDERDRAINS OTHER THAN THOSE SHOWN ON THE PLANS, HE/SHE SHALL INFORM THE ENGINEER, WHO SHALL DIRECT THE WORK NECESSARY TO MAINTAIN OR REPLACE THE FACILITIES IN SERVICE AND TO PROTECT THEM FROM DAMAGE DURING CONSTRUCTION IF MAINTAINED. EXISTING FACILITIES TO BE MAINTAINED THAT ARE DAMAGED BECAUSE OF NON-COMPLIANCE WITH THIS PROVISION SHALL BE REPLACED AT THE CONTRACTOR'S OWN EXPENSE.
- THE CONTRACTOR SHALL PROVIDE TEMPORARY TOILET FACILITIES AND HAND SANITIZING STATIONS FOR THE USE OF ALL THE CONTRACTORS PERSONNEL EMPLOYED ON THE WORK SITE. THE FACILITIES SHALL BE MAINTAINED IN PROPER SANITARY CONDITION THROUGHOUT THE PROJECT. THE LOCATION OF THE TEMPORARY FACILITIES SHALL BE APPROVED BY THE ENGINEER.
- 10. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE NPDES PERMIT AND SWPPP MANUAL. IF NO NPDES PERMIT OR SWPPP MANUAL IS NEEDED FOR THE PROJECT THE CONTRACTOR SHALL PERFORM SOIL EROSION SEDIMENT CONTROL BEST PRACTICES OR AS DIRECTED BY THE OWNER TO PREVENT ILLICIT DISCHARGES FROM THE SITE.

UTILITY NOTES

- UNDERGROUND WORK SHALL INCLUDE TRENCHING, DISPOSAL OF EXCESS MATERIAL, DEWATERING, INSTALLATION OF PIPE, CASTINGS, STRUCTURES, BACKFILLING OF TRENCHES AND COMPACTION, AND TESTING AS SHOWN ON THE CONSTRUCTION PLANS. FITTINGS AND ACCESSORIES NECESSARY TO COMPLETE THE WORK MAY NOT BE SPECIFIED BUT SHALL BE CONSIDERED AS INCLUDED TO THE COST OF THE CONTRACT. ALL SEWER SHALL BE INSTALLED USING A LASER AND BEGIN AT THE DOWNSTREAM END.
- MACHINE CORE ALL CONNECTIONS TO EXISTING STRUCTURES USING A CORE DRILL. HAMMERING OR SAWING OF STRUCTURES WILL NOT BE ALLOWED.
- SANITARY SERVICE CONNECTIONS TO NEW SEWERS SHALL BE MADE WITH WYE BRANCHES. WYE BRANCHES SHALL BE FACTORY MANUFACTURED PERMANENTLY AFFIXED TO THE MAIN SEWER. TEE BRANCHES ARE NOT ALLOWED.
- ALL CONNECTIONS TO EXISTING SANITARY MANHOLES SHALL BE INSTALLED WITH A NEOPRENE BOOT SECURED WITH DOUBLE STAINLESS STEEL STRAPS MEETING THE REQUIREMENTS OF ASTM C-923.
- ALL CONNECTIONS TO EXISTING OR DISSIMILAR STORM/SANITARY LINES SHALL BE DONE WITH STAINLESS STEEL NON-SHEAR COUPLINGS.
- STONE BEDDING AND BACKFILL SHALL BE OMITTED FOR A DISTANCE OF 15 FEET UP AND DOWNSTREAM OF SEWERS DRAINING TO OR FROM PONDS OR STREAMS. THE REPLACED BEDDING SHALL BE SILTY CLAY SOIL MECHANICALLY COMPACTED TO 90% MODIFIED PROCTOR DENSITY. THE USE OF PERMEABLE 22. SOILS WILL NOT BE PERMITTED.
- ALL WATER MAIN SHALL HAVE MECHANICAL RESTRAINED TYPE JOINTS AT ALL CONNECTIONS AND FITTINGS. IN ADDITION, ALL HARDWARE SHALL BE STAINLESS STEEL.
- THRUST BLOCKING SHALL BE PROVIDED ON WATER MAIN AT ALL BENDS, TEES, ELBOWS, ETC. INDIVIDUAL INSPECTION FOR ALL THRUST BLOCKING IS REQUIRED. THRUST BLOCKING SHALL BE POURED IN PLACE CONCRETE. PRECAST BLOCKS MAY BE USED AS APPROVED BY THE ENGINEER IN THE FIELD. 24. ALL SIGNAGE SHALL BE INSTALLED IN ACCORDANCE WITH THE MOST RECENT VERSION OF THE
- ALL FLOOR DRAINS SHALL DISCHARGE TO THE SANITARY SEWER. ALL DOWNSPOUTS, SIDE YARD DRAINS, AND OUTSIDE DRAINS SHALL DISCHARGE TO THE STORM SEWER SYSTEM. FOOTING DRAINS SHALL FIRST DRAIN TO A SUMP PIT.

NON-WOVEN

LIGHT DUTY

PROJECT SPECIFIC NOTES

- 1. THE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS THAT INCLUDE; CRITICAL SPOT GRADES SUCH AS OVERFLOW ELEVATIONS, SPOT ELEVATIONS NEAR ENTRANCES, SPOT ELEVATIONS ALONG THE DESIGNATED ADA ROUTE, SUFFICIENT INFORMATION SUCH THAT THE ENGINEER MAY VERIFY DETENTION VOLUMES, RIM AND INVERT ELEVATIONS OF ALL SEWERS, RIM AND TOP OF PIPE ELEVATIONS OF ALL WATER MAIN, LOCATIONS OF ALL INSTALLED UNDERGROUND UTILITIES, LOCATIONS OF ALL BURIED BENDS AND FITTINGS AND ALL FIELD CHANGES FROM THE APPROVED DRAWINGS.
- 2. ALL WORK PERFORMED UNDER THIS CONTRACT SHALL BE GUARANTEED BY THE CONTRACTOR AND HIS SURETY FOR A PERIOD OF 12 MONTHS FROM THE DATE OF INITIAL ACCEPTANCE OF THE WORK BY THE OWNER AGAINST ALL DEFECTS IN MATERIALS AND WORKMANSHIP OF WHATEVER NATURE.
- ALL CONSTRUCTION WILL BE INSPECTED BY THE OWNER'S REPRESENTATIVE. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE MUNICIPALITY AS WELL AS THE STANDARD SPECIFICATIONS.
- ALL PUBLIC WATER MAINS AND SANITARY SEWER MAINS MUST BE ACCEPTED BY THE VILLAGE OF
- VILLAGE OF BUFFALO GROVE BEFORE WORK IS STARTED.
- CONTRACTOR SHALL NOTIFY THE VILLAGE OF BUFFALO GROVE (847-457-2500) AND THE PROJECT ENGINEER (847-478-9700) AT LEAST 72 HOURS PRIOR TO BEGINNING ANY WORK ON THIS
- THE CONTRACTOR SHALL INDEMNIFY THE OWNER, ENGINEER, THE MUNICIPALITY AND THEIR AGENTS. FROM ALL LIABILITY INVOLVED IN CONSTRUCTION, INSTALLATION AND TESTING OF THE WORK ON THIS PROJECT.
- THE CONTRACTOR MUST CARRY INSURANCE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. ALL OFFICIALS, EMPLOYEES AND AGENTS OF GEWALT HAMILTON ASSOCIATES MUST BE LISTED AS ADDITIONAL INSURED.
- 9. ALL ELEVATIONS ARE ON NAVD 88 VERTICAL DATUM.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL TRAFFIC CONTROL TO ADEQUATELY INFORM AND PROTECT THE PUBLIC OF ALL CONSTRUCTION OPERATIONS.
- 11. STOCKPILING MATERIAL WITHIN THE 100 YEAR FLOOD PLAIN AND OR THE FLOODWAY IS STRICTLY PROHIBITED
- 12. PRIOR TO PLACEMENT OF FABRIC AND STONE, THE SUBGRADE SHALL BE PROOF-ROLLED IN THE PRESENCE OF THE ENGINEER. PROOF-ROLLING SHALL BE DONE USING A THREE AXLE DUMP TRUCK TOGETHER WITH LOAD WEIGHING AT LEAST TWENTY-FIVE (25) TONS. THE LOAD SHALL BE UNIFORMLY PLACED IN THE DUMP BODY. ALL DEFICIENCIES SHALL BE REPAIRED AND RE-PROOF-ROLLED UNTIL FOUND ACCEPTABLE TO THE ENGINEER.
- 13. CRUSHED CONCRETE IS NOT PERMITTED FOR USE ON THE PROJECT UNLESS PRIOR WRITTEN NOTICE IS GIVEN BY THE ENGINEER.
- 14. ALL STONE USED ON THE PROJECT SHALL BE CRUSHED UNLESS SPECIFICALLY NOTED OTHERWISE.
- 15. ALL CONNECTIONS TO EXISTING STORM MANHOLES SHALL BE INSTALLED WITH A NEOPRENE BOOT SECURED WITH DOUBLE STAINLESS STEEL STRAPS MEETING THE REQUIREMENTS OF ASTM C-923.
- 16. ALL CONCRETE SHALL HAVE A LIGHT BROOM FINISH APPLIED WITHIN 1 HOUR OF FINAL STRIKING.
- 17. ALL CONCRETE SHALL CONSIST OF PORTLAND CEMENT CONCRETE MEETING REQUIREMENTS OF SECTION 1020. ALL SIDEWALKS, CURBS AND POST FOUNDATIONS SHALL BE CLASS SI 3,500 PSI @ 14 DAYS. ALL PAVEMENT SHALL BE CLASS PV 3,500 PSI @ 14 DAYS. WHERE NOTED ON THE PLANS HIGH EARLY CONCRETE SHALL BE CLASS PV TYPE III 3,500 PSI CONCRETE @ 3 DAYS. ALL CONCRETE REQUIRING A CURE TIME FASTER THAN 3 DAYS SHALL HAVE A MIX DESIGN SUBMITTED TO THE ENGINEER FOR APPROVAL. WHEN REQUIRED BY THE MUNICIPALITY, FLY ASH SHALL NOT BE USED IN THE MIX DESIGN. SLUMP SHALL BE 2-4" AND AIR CONTENT SHALL BE BETWEEN 5-8% UNLESS MODIFIED BY ARTICLE 1020.04.
- 18. ALL CONCRETE SHALL HAVE A WHITE, IDOT TYPE 3 CURING COMPOUND APPLIED TO THE SURFACE WITHIN 1 HOUR OF FINAL STRIKING AT THE MANUFACTURER RECOMMENDED APPLICATION RATE.
- 19. 3/4" THICK PRE-MOLDED FIBER EXPANSION JOINTS WITH 2, 3/4" x 18" PLAIN ROUND, STEEL DOWEL BARS SHALL BE INSTALLED IN ALL CURBS AT (45') FORTY-FIVE FOOT INTERVALS AND AT ALL P.C.'S. P.T.'S AND CURB RETURNS. ALTERNATE ENDS OF THE DOWEL BARS SHALL BE GREASED. AND FITTED WITH METAL EXPANSION TUBES. ALL EXPANSION JOINTS MUST BE FREE OF CONCRETE FOR FULL DEPTH. CONTRACTION JOINTS SHALL BE TOOLED AT 15' INTERVALS.
- 20. UNLESS OTHERWISE NOTED ON THE PLANS WHENEVER NEW CONCRETE ABUTS EXISTING/ OR NEW CONCRETE SET A 1/2" THICK PRE-MOLDED FIBER EXPANSION JOINT AND DOWEL WITH SMOOTH 12" #4 BARS @ 24" O.C. THIS INCLUDES CONCRETE POURED ADJACENT TO EXISTING SIDEWALKS. CURBS AND BUILDING. THE DOWEL BARS SHOULD BE 4" INTO EXISTING CONCRETE WITH 8" EXTENDING INTO NEW CONCRETE.
- 21. ALL DOWEL BARS AND TIE BARS SHALL BE EPOXY COATED UNLESS NOTED OTHERWISE.
- ALL PAVEMENT AND BUILDING SUBGRADE SHALL BE COMPACTED TO 95% MODIFIED PROCTOR DENSITY (ASTM D-1557). ALL SUBGRADE IN LAWN AREAS SHALL BE COMPACTED TO 90% MODIFIED PROCTOR DENSITY (ASTM D-1557). ALL TOPSOIL AND SUBGRADE 6" BELOW TOPSOIL SHALL BE COMPACTED TO 80% STANDARD PROCTOR DENSITY (ASTM D-698)
- 23. SPREAD SCREENED TOPSOIL ON ALL DISTURBED AREAS AND PROPOSED GREEN AREAS. TOPSOIL SHALL COMPLY WITH REQUIREMENTS OF ARTICLE 1081.05.
- MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND ILLINOIS SUPPLEMENT OR ILLINOIS DEPARTMENT OF TRANSPORTATION DETAILS.
- 25. ALL SIGNAGE NOT ATTACHED TO SIGNAL OR LIGHTING POLES SHALL BE MOUNTED ON TELESCOPING STEEL SIGN SUPPORTS WITH BREAKAWAY BASES IN ACCORDANCE WITH SECTION 728.
- 26. ALL SIGNAGE SHALL HAVE TYPE ZZ SHEETING.

MINIMUM GRAD TENSILE ASTM D4632 = 90 LBS

MINIMUM TRAPEZOID TEAR ASTM D4533 = 40 LBS

MINIMUM FLOW RATE ASTM D4491 = 150 GAL/MIN/SQFT

STANDARDS/REQUIREMENTS

EROSION CONTROL NOTES

- 1. AT A MINIMUM, THE CONTRACTOR SHALL INSTALL AND MAINTAIN SOIL EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES IN ACCORDANCE WITH THE REQUIREMENTS SET FORTH IN THE LATEST EDITION OF THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY'S URBAN MANUAL.
- 2. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS.
- 3. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ANY ROAD OF MATERIAL THAT IS FROM THE PROJECT. THIS WILL BE DONE AT THE CLOSE OF EACH DAY OF WORK OR MORE FREQUENTLY AS FIELD CONDITIONS WARRANT.
- 4. ALL STORM WATER STRUCTURES WITH OPEN LIDS SHALL BE PROTECTED WITH INLET FILTER BASKETS. DURING CONSTRUCTION, SEDIMENT SHALL BE REMOVED AS NEEDED, AND BASKETS SHALL BE REPAIRED OR REPLACED AS NEEDED.
- THE SEWER AND WATER CONTRACTOR SHALL BE REQUIRED TO BE LICENSED AND BONDED WITH THE 5. AFTER ACHIEVING PERMANENT VEGETATION, ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE REMOVED, AND THE DRAINAGE STRUCTURES SHALL BE CLEANED
 - 6. THE CONTRACTOR SHALL KEEP A WATER SOURCE AT THEIR DISPOSAL FOR THE PURPOSE OF WATERING DOWN SOIL ON SITE AND ADJACENT ROADWAYS WHICH OTHERWISE MAY BECOME AIRBORNE.
 - 7. THE CONTRACTOR SHALL STABILIZE ALL IDLE, DISTURBED AREAS WITHIN SEVEN DAYS OF CESSATION OF THE CONSTRUCTION ACTIVITIES IN THAT AREA.
 - 8. THE CONTRACTOR IS EXPRESSLY ADVISED NOT TO DISTURB AREAS WHICH ARE OUTSIDE THOSE NECESSARY TO PROVIDE THE IMPROVEMENTS AS CALLED FOR IN THE PLANS.
 - 9. ALL EROSION CONTROL MEASURES SHALL BE REPLACED IF DAMAGED OR MAINTAINED THROUGHOUT THE LIFE OF THE PROJECT.
 - 10. ALL BYPASS CHANNELS, MUST BE CONSTRUCTED SO THAT CHANNEL FLOWS WILL NOT CAUSE EROSION OF EXCAVATED MATERIAL. IN EACH CASE A SEDIMENTATION BASIN MUST BE CONSTRUCTED SO AS TO ALLOW THE SEDIMENT TO SETTLE PRIOR TO THE DOWNSTREAM OUTLET OF THE PROJECT AREA.
 - 11. PUMPS MAY BE USED AS BYPASS DEVICES. BUT IN NO CASE WILL THE WATER BE DIVERTED OUTSIDE THE PROJECT LIMIT. ALL PUMPED WATER SHALL BE FREE OF SILT. PUMPING MAY REQUIRE THE USE OF A SEDIMENT CONTAINMENT FILTER BAG AND OTHER SUPPLEMENTAL SEDIMENT CONTROL MEASURES.
 - 12. CONCRETE WASHOUT FACILITIES SHALL BE MADE AVAILABLE IF NEEDED, AND PROPERLY MAINTAINED THROUGHOUT THE PROJECT.
 - 13. PROPERLY MANAGE ALL MATERIAL STORAGE AREAS, PORTABLE TOILETS, AND EQUIPMENT FUELING, CLEANING, AND MAINTENANCE AREAS TO ENSURE THESE AREAS ARE FREE OF SPILLS, LEAKS, OR OTHER POTENTIAL POLLUTANTS.
 - 14. WASTE, CONSTRUCTION DEBRIS, AND BUILDING MATERIALS SHALL BE COLLECTED AND PLACED IN APPROVED RECEPTACLES.

JOINT: ASTM D-3212

JOINT: ASTM D-3212

REVISION

CRUSHED CONCRETE NOT ALLOWED, ALL STONE MUST BE WASHED

STORMWATER MANAGEMENT COMMISSION

TYPICAL CONSTRUCTION SEQUENCING

- Installation of soil erosion and sediment control SE/SC measures
- Selective vegetation removal for silt fence installation Silt fence installation
- Construction fencing around areas not to be disturbed c.)
- Stabilized construction entrance
- 2.) Tree removal where necessary (clear & grub)
- 3.) Construct sediment trapping devices (sediment traps, basins...)
- 4.) Construct detention facilities and outlet control structure with restrictor & temporary perforated riser
- 5.) Strip topsoil, stockpile topsoil and grade site
- 6.) Temporarily stabilize topsoil stockpiles (seed and silt fence around toe of slope)
- 7.) Install storm sewer, sanitary sewer, water and associated inlet & outlet protection
- 8.) Permanently stabilize detention basins with seed and erosion control blanket
- 9.) Temporarily stabilize all areas including lots that have reached temporary grade
- 10.) Install roadways

MEASURES.

- 11.) Permanently stabilize all outlot areas
- 12.) Install structures and grade individual lots
- 13.) Permanently stabilize lots
- 14.) Remove all temporary SE/SC measures after the site is stabilized with vegetation
- Soil erosion and sediment control maintenance must occur every two weeks and after every ½ or greater rainfall event

LAKE COUNTY STORMWATER MANAGEMENT COMMISSION SOIL EROSION AND SEDIMENT CONTROL CONSTRUCTION NOTES

- A. SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF HYDROLOGIC DISTURBANCE OF UPLAND AREAS.
- B. FOR THOSE DEVELOPMENTS THAT REQUIRE A DESIGNATED EROSION CONTROL INSPECTOR (DECI), INSPECTIONS AND DOCUMENTATION SHALL BE PERFORMED, AT A MINIMUM:
 - UPON COMPLETION OF SEDIMENT AND RUNOFF CONTROL MEASURES (INCLUDING PERIMETER CONTROLS AND DIVERSIONS), PRIOR TO PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. • AFTER EVERY SEVEN (7) CALENDAR DAYS OR STORM EVENT WITH GREATER THAN 0.5 INCH OF RAINFALL OR LIQUID
- EQUIVALENT PRECIPITATION. C. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. IF STRIPPING, CLEARING, GRADING, OR

LANDSCAPING ARE TO BE DONE IN PHASES, THE PERMITTEE SHALL PLAN FOR APPROPRIATE SOIL EROSION AND SEDIMENT CONTROL

- D. A STABILIZED MAT OF CRUSHED STONE MEETING IDOT GRADATION CA-1 UNDERLAIN WITH FILTER FABRIC AND IN ACCORDANCE WITH THE ILLINOIS URBAN MANUAL, OR OTHER APPROPRIATE MEASURE(S) AS APPROVED BY THE ENFORCEMENT OFFICER. SHALL BE INSTALLED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION SITE. SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING AREA SHALL BE REMOVED BY SCRAPING OR STREET CLEANING AS
- E. TEMPORARY DIVERSIONS SHALL BE CONSTRUCTED AS NECESSARY TO DIRECT ALL RUNOFF FROM HYDROLOGICALLY DISTURBED AREAS TO AN APPROPRIATE SEDIMENT TRAP OR BASIN.
- F. DISTURBED AREAS SHALL BE STABILIZED WITH TEMPORARY OR PERMANENT MEASURES WITHIN SEVEN (7) CALENDAR DAYS FOLLOWING THE END OF ACTIVE HYDROLOGIC DISTURBANCE OR REDISTURBANCE.

ACCUMULATIONS WARRANT AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.

- G. ALL STOCKPILES SHALL HAVE APPROPRIATE MEASURES TO PREVENT EROSION. STOCKPILES SHALL NOT BE PLACED IN FLOOD PRONE AREAS OR WETLANDS AND DESIGNATED BUFFERS.
- H. SLOPES STEEPER THAN 3H:1V SHALL BE STABILIZED WITH APPROPRIATE MEASURESAS APPROVED BY THE ENFORCEMENT OFFICER.
- I. APPROPRIATE EROSION CONTROL BLANKET SHALL BE INSTALLED ON ALL INTERIOR DETENTION BASIN SIDE SLOPES BETWEEN THE NORMAL WATER LEVEL AND HIGH WATER LEVEL.
- J. STORM SEWERS THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED BY AN APPROPRIATE SEDIMENT CONTROL MEASURE
- K. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION. DISCHARGES SHALL BE ROUTED THROUGH AN APPROVED ANIONIC POLYMER DEWATERING SYSTEM OR A SIMILAR MEASURE AS APPROVED BY THE ENFORCEMENT OFFICER. DEWATERING SYSTEMS SHOULD BE INSPECTED DAILY DURING OPERATIONAL PERIODS. THE ENFORCEMENT OFFICER, OR APPROVED REPRESENTATIVE, MUST BE PRESENT AT THE COMMENCEMENT OF DEWATERING ACTIVITIES.
- L. IF INSTALLED SOIL EROSION AND SEDIMENT CONTROL MEASURES DO NOT MINIMIZE SEDIMENT LEAVING THE DEVELOPMENT SITE, ADDITIONAL MEASURES SUCH AS ANIONIC POLYMERS OR FILTRATION SYSTEMS MAY BE REQUIRED BY THE ENFORCEMENT OFFICER.
- M. ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE PROPERTY OWNER SHALL BE ULTIMATELY RESPONSIBLE FOR MAINTENANCE AND REPAIR.
- N. ALL TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.
- O. THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER, ENFORCEMENT OFFICER, OR OTHER GOVERNING AGENCY.

U:\Regulatory Program\SESC handouts\SE-SC Notes 2013 TAC-approved.doc

SHEET NUMBER:

of 12 sheets

FILE: 4647.156 DT1.dwg DRAWN BY: DGC GHA PROJECT # **DATE:** 12-05-22 4647.022 CHECKED BY: JMB | SCALE: **DATE:** 12-05-22 N.T.S. NO. BY DATE **REVISION**

COPYRIGHT NOTICE This drawing is the property of Gewalt—Hamilton Assoc., Inc. and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from Gewalt-Hamilton Associates, Inc.

STYLE DESCRIPTION

UNDERDRAIN FABRIC

GENERAL NOTES & SESC NOTES BUFFALO GROVE PARK DISTRICT

GEWALT HAMILTON ASSOCIATES, INC. 625 Forest Edge Drive ■ Vernon Hills, IL. 60061 TEL 847.478.9700 FAX 847.478.9701

2023 RYLKO PARK IMPROVEMENTS - INLINE SKATE RINK REDEVELOPMENT **BUFFALO GROVE, ILLINOIS 60089**

STORM SEWERS

JNDERDRAINS

FRAME & GRATE/LID

ADJUSTMENT RINGS

TRENCH BACKFILL

PIPE BEDDING MATERIAL

TRENCH BACKFILL UNDERDRAIN CA7/CA-11

MODEL/SPECIFICATION | STANDARDS/REQUIREMENTS

PIPE:ASTM D-3034

PIPE:ASTM D-3034

CLOSED LID: NEEENAH R-1976

4" MINIMUM, 12" MAXIMUM

OPEN LID: NEENAH R-4350-B TYPE 8

NO. BY DATE

PVC SDR 26

PVC SDR 26


GRASS AREAS


CLEANOUT


CONCRETE


CA-11


CA-6

















LEGEND


GEWALT HAMILTON ASSOCIATES, INC. 625 Forest Edge Drive Vernon Hills, IL. 60061 TEL 847.478.9700 FAX 847.478.9701

COPYRIGHT NOTICE This drawing is the property of Gewalt—Hamilton Assoc., Inc. and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from Gewalt—Hamilton Associates, Inc.

CROSS SECTIONS
2023 RYLKO PARK IMPROVEMENTS
BUFFALO GROVE PARK DISTRICT
BUFFALO GROVE, ILLINOIS

						FILE: 4647.156 PR1.dwg		
						DRAWN BY: DGC DATE: 12-05-22	GHA PRC 4647	
NO. BY	DATE	REVISION	NO. BY	DATE	REVISION	CHECKED BY: JMB DATE: 12-05-22		

SHEET NUMBER: DGC GHA PROJECT # 4647.155 of 12 sheets



Project Type (From ab Project Category (From Above)	Media File #/Name	Project Category Cost	_ Α	ADA Portion of Project Cate % ADA Dollars Requ	uested
Routes and Surfaces Design Services	Upland_Design_InLine		19400	1940	10.00%
Routes and Surfaces Accessible Routes	Hacienda_InLine		22940	14337.5	62.50%
Routes and Surfaces Walking Surfaces	Hacienda_InLine		10200	6375	62.50%
Routes and Surfaces Walking Surfaces	_ Hacienda_InLine		15552	9720	62.50%
0	_			#DIV/0!	
				#DIV/0! #DIV/0!	
				#DIV/0!	
				#DIV/0:	

#DIV/0!

Total Project Cost68092Total ADA Portion of Project Cost32372.5Total % of ADA Dollars Requested47.54%